

			Type of Feeder		LOAD CALCULATION						CONSUMED LOAD						REMARKS
Sl. No.	Equipment Tag	Description		Voltage Rating	Absorbed Load (X)	Rated Load (Y)	Load Factor Z = X/Y	Efficiency at Load Factor Z	Power Factor at Load Factor Z	Load Duty: C/I/S	Continuous		Intermittent		Stand-By		
											kW	kVA _r	kW	kVA _r	kW	kVA _r	
1	U-3601-01A	Compressor-1 Auxiliary Load	Feeder	415	11.00	11.00	1.00	0.94	0.86	C	12	0.0	0.0	0.0	0.0	0.0	
2	U-3601-01B	Compressor-2 Auxiliary Load	Feeder	415	11.00	11.00	1.00	0.94	0.86	C	12	0.0	0.0	0.0	0.0	0.0	
3	U-3601-01C	Compressor-3 Auxiliary Load	Feeder	415	11.00	11.00	1.00	0.94	0.86	C	12	0.0	0.0	0.0	0.0	0.0	
4	U-3601-01D	Compressor-4 Auxiliary Load	Feeder	415	11.00	11.00	1.00	0.94	0.86	S	0	0.0	0.0	0.0	11.8	0.0	
5	U-3601-01A/B/C/D	Compressor Package Hot Startup Load	Feeder	415	24.00	24.00	1.00	0.94	0.86	I	0	0.0	25.7	0.0	0.0	0.0	
6	P-3601-02A	HC Condensate pump-A	DOL	415	49.09	60.00	0.82	0.94	0.86	C	53	31.2	0.0	0.0	0.0	0.0	
7	P-3601-02B	HC Condensate pump-B	DOL	415	49.09	60.00	0.82	0.94	0.86	S	0	0.0	0.0	0.0	52.5	31.2	
8	P-6701-01A	Closed Drain Flare KO Pump-A	DOL	415	3.60	5.00	0.72	0.94	0.86	C	4	0.0	0.0	0.0	0.0	0.0	
9	P-6701-01B	Closed Drain Flare KO Pump-B	DOL	415	3.60	5.00	0.72	0.94	0.86	C	4	0.0	0.0	0.0	0.0	0.0	
10	U-1601-01/ U-6901-01	Instrument Air & N2 package-Unit-1	Star Delta	415	61.36	75.00	0.82	0.94	0.86	C	66	0.0	0.0	0.0	0.0	0.0	Combined I2 and N2 Pacakge. Lead Lag
11	U-1601-01/ U-6901-01	Instrument Air & N2 package-Unit-2	Star Delta	415	61.36	75.00	0.82	0.94	0.86	C	66	0.0	0.0	0.0	0.0	0.0	Combined I2 and N2 Pacakge. Lead Lag
12	G-4101-01A	Gas Power Generator Auxiliary DB	Feeder	415	40.00	40.00	1.00	0.94	0.86	C	43	0.0	0.0	0.0	0.0	0.0	
13	G-4101-01B	Gas Power Generator Auxiliary DB	Feeder	415	40.00	40.00	1.00	0.94	0.86	S	0	0.0	0.0	0.0	42.8	0.0	
14	P-2301-01	Potable Water Pump	DOL	415	3.60	5.00	0.72	0.94	0.86	C	4	0.0	0.0	0.0	0.0	0.0	
15	-	Chemical Injection Pump-A	DOL	415	0.36	0.50	0.72	0.94	0.86	I	0	0.0	0.4	0.0	0.0	0.0	Hold
16	-	Chemical Injection Pump-B	DOL	415	0.36	0.50	0.72	0.94	0.86	S	0	0.0	0.0	0.0	0.4	0.0	Hold
17	-	230VAC UPS	Feeder	415	60.00	60.00	1.00	0.94	0.86	C	64	0.0	0.0	0.0	0.0	0.0	Preliminary
18	-	Lighting and Small Power	Feeder	415	25.00	25.00	1.00	0.94	0.86	C	27	0.0	0.0	0.0	0.0	0.0	
19	-	HAVC and Other Plant AC Load	Feeder	415	50.00	50.00	1.00	0.94	0.86	C	53	0.0	0.0	0.0	0.0	0.0	
20	-	Welding Outlet 1 & 2	Feeder	415	37.00	37.00	1.00	0.94	0.86	I	0	0.0	39.6	0.0	0.0	0.0	
21	-	Welding Outlet 3 & 4	Feeder	415	37.00	37.00	1.00	0.94	0.86	I	0	0.0	39.6	0.0	0.0	0.0	
22	P-3601-01A	1st Stage Condensate Pump	DOL	415	3.60	5.00	0.72	0.94	0.86	C	4	0.0	0.0	0.0	0.0	0.0	
23	P-3601-01B	1st Stage Condensate Pump	DOL	415	3.60	5.00	0.72	0.94	0.86	C	4	0.0	0.0	0.0	0.0	0.0	
24	P-3601-01C	1st Stage Condensate Pump	DOL	415	3.60	5.00	0.72	0.94	0.86	C	4	0.0	0.0	0.0	0.0	0.0	
25	P-3601-01D	1st Stage Condensate Pump	DOL	415	3.60	5.00	0.72	0.94	0.86	S	0	0.0	0.0	0.0	3.9	0.0	
										Sub Total	429	31	105	0	111	31	
							TOTALS	In kW and kVA _r			429.32	31.15	105.20	0.00	111.28	31.15	
Maximum running load, kW = (x% . SE) + (y% . SF)					kVA	473.57		kVA = (kW ² + kVA _r ²)			430.5		105		116		


